

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>			1. CONTRACT ID CODE	PAGE 1 OF 3 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0004		3. EFFECTIVE DATE 09/18/09	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 08-0094
6. ISSUED BY CODE		CODE	7. ADMINISTERED BY (If other than Item 6) CODE	
Officer in Charge of Construction MCI-East 1005 Michael Road Camp Lejeune, NC 28547-2521		See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-08-R-0094
			X	9B. DATED (SEE ITEM 11) 09/04/09
				10A. MODIFICATION OF CONTRACT/ORDER NO.
				10B. DATED (SEE ITEM 11)
CODE	FACILITY CODE			

**11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers  is extended,  is not extended.  
 Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:  
 (a) By completing items 8 and 15, and returning \_\_\_\_\_ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;  
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.  
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor  is not,  is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

08-0094, ARRA, AS705 Renovation

(CONTINUED)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	
15C. DATE SIGNED		16C. DATE SIGNED	
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

CONTINUATION SHEET

1. Delete the requirement for a heat pipe on HRU-1. This is shown on M-602.
2. Question: I cannot find anything about the bedding required for the pipe. Please clarify.
2. Answer: Provide #57 stone for bedding underground piping.
3. Question: What type of cook top surface is required and what size are the surface elements? The Range oven calls for tempered glass control panels. This is very expensive material. Can this be substituted with industry standard material to lower the cost?
3. Answer: Industry standard 30" ranges with solid surface cook top, continuous cleaning or self cleaning oven, and manufacture's standard controls are acceptable.
4. Question: Demo Not # 18; Drawing AD102 - Indicates that the Stove and microwave is to be removed. Are these appliances to be removed and disposed of or is the contractor to remove and store for reinstallation?
4. Answer: Drawing AD102 Demo Note # 18; Revise to indicate demolition of range and microwave.
5. Question: Please advise the size of the underground storage tank scheduled for demolition. Also advise if the tank contains any fuel oil and who will be responsible for removal of any oil.
5. Answer: The contractor shall remove existing 4000 gallon fiberglass underground storage tank. The contractor shall remove and dispose of the contents of the tank.
6. Question: Can the Project Superintendent, SSHO and QC be the same individual if duly qualified?
6. Answer: The same individual may serve as Project Superintendent, SSHO and QC if qualified.
7. Question: Amendment 1 Specifications state - A temporary laundry area will be established in the existing kitchen area in an area to be determined by the contracting officer. The Contractor shall relocate washers and dryers to the designated location and provide temporary plumbing, ducting of dryer vents and electrical power connections for operation of the laundry equipment. Question: Can you provide a "Bulletin" Drawing identifying the details of this temporary relocation of washers and dryers? Will the Contractor be required to provide make-up air?
7. Answer: No make up air will be required for temporary laundry.
8. Question: Who is responsible for the removal and storage of the existing furniture, refrigerators and microwaves? Due to the type of furniture, it is recommended that the furniture be stored in a climate controlled unit. There are no specifications telling us who

removes, stores, nor how (i.e., climate controlled unit, etc.) the furniture will be handled. If the contractor is responsible for the removal and storage of the furniture, will each piece of furniture be required to be placed in the same room it was removed? Who is responsible for the removal and storage/disposal of miscellaneous wall paintings, mirrors, pictures, decorations and plants? Who is responsible for the removal and reinstallation of the Sauna and nautilus weight lifting equipment in room 113 for the asbestos removal and new work?

8. Answer: The contractor shall remove, store, protect all furnishings, sauna, weight lifting equipment, appliances, furniture, paintings, mirrors, decorations, and plants. The contractor shall provide climate controlled storage for all. The contractor will not be required to return the contents to the specific room from which the items were removed.
9. Question: The demo notes indicate to remove piping back to the chase wall, however, there are no requirements to “cap” the lines that are being abandoned. Will capping of the lines be required?
9. Answer: Where pipes are demolished, provide caps or plugs as required to seal the piping to remain.
10. Question: The drawings indicate to demo the existing chimney complete, however, in some storage rooms, there are electrical panels with 1" & 2" conduit mounted on the chimney. It also appears that the chimney walls are shared walls by adjacent rooms that may leave openings if it is removed. Is it possible to leave the chimney intact and permanently cap the top on the roof and abandon the chimney in place?
10. Answer: Demolish the chimney down to below the surface of the roof slab. Fill and level the opening in the roof slab with concrete. Delete the requirement to demolish the chimney complete.
11. Question: Section 01 58 00 requires a sign for Project Identification. Will this be required?
11. Answer: Delete requirement for project identification sign.
12. Question: In order to remove the existing steel tubs, 1 to 2 rows of the existing perimeter ceramic tile will have to be removed. On the architectural drawings, requirements are for new 4 piece tubs with surrounds to be installed. Is it the intent to install the surrounds over the existing ceramic tile?
12. Answer: In all motel rooms demolish existing thickset ceramic tile. Provide new thickset ceramic tile in motel rooms. Remove existing toilets scheduled to remain as required to perform other work.
13. Provide concrete pads for two 1000 gal LP tanks. The government will contract with Jenkins gas for the tanks and gas.
14. Provide acrylic reinforced with fiberglass 4 piece tubs. Provide concrete under tub to support floor of tub.