

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>			1. CONTRACT ID CODE	PAGE 1 OF 2 PAGES
2. AMENDMENT/MODIFICATION NO. 0005	3. EFFECTIVE DATE 3/2/10	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable)	
6. ISSUED BY OFFICER IN CHARGE OF CONSTRUCTION MCI EAST 1005 MICHAEL ROAD, CAMP LEJEUNE, NC 28547-2521	CODE N40085	7. ADMINISTERED BY (If other than Item 6) SEE ITEM 6		CODE
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO.
				9B. DATED (SEE ITEM 11)
			(X)	10A. MODIFICATION OF CONTRACT/ORDER NO. N40085-09-R-0149
				10B. DATED (SEE ITEM 11) 2/4/10
CODE 338T2	FACILITY CODE			

**11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers  is extended,  is not extended.  
 Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:  
 (a) By completing items 8 and 15, and returning \_\_\_\_\_ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;  
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.  
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor  is not,  is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

09-0149 REPAIR APPLIED INSTRUCTION, BLDG BB48

BID OPENING IS HEREBY CHANGED FROM 2 MARCH 2010 @ 1:00 PM TO 5 MARCH 2010 @ 9:00 AM

See Continuation Page (s)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

SUMMARY OF CHANGES:

THE PROJECT IS TO BE BID AS FOLLOWS:

ITEM 0001: ALL WORK FOR THE REPAIR OF BLDG BB48, INCLUDING WORK ASSOCIATED WITH THE TEMP FACILITIES.

ITEM 0002: ALL INSIDE/OUTSIDE PLANT TELECOMMUNICATIONS WORK, TO INCLUDE INSTALLATION/REPLACEMENT OF CONDUIT, WIRING, BACKBOARD, JACKS, ETC. FOR BLDG BB48.

RESPONSES TO INQUIRIES:

Question: 1. What is the size and location of the water meter to be added in amendment 4?

-Response: Water meter shall be located on water service line inside the mechanical room. Water service to building is 2.5".

Question 2: Please clarify where the 2 – 4” conduits for the telecom wiring in the trailer are supposed to come from.

-Response: Contractor shall use the telecomm service from BB48 for the trailer.

Question 3: It is not clear on the asbestos survey - How much asbestos piping insulation is on the project, that needs to be abated?

-Response: See Hazardous Containing Materials Note, Sheet D-1.

Question 4: On sheet A-1 Note 11 tells us to install new heaters in the High Bay Area. See Mechanical Drawings. Note 11 shows up in most rooms. The mechanical plans only show 2 infrared heaters. Are these the only two heaters to be put in?

-Response: Sheet A-1, Delete note 11. Contractor shall install the two infrared heaters shown on Sheet M1.1-Renovation Plan.

Question 5: The Mechanical demo notes tell us to remove all steam & condensate pipe. Does this include removing the existing lines outside to the main and the existing 5 concrete poles? If so, is it acceptable to cut the poles off below grade and cover due to the large amount of concrete at the base of poles under the ground, or would they need to be removed completely?

-Response: Demolish steam and condensate laterals from building to the distribution main, including the support poles. Poles may be cut off 24" below grade, fill in holes to match existing surrounding grade.

Question 6: Will the condensing units be required to have the protective coating applied to the coils?

-Response: Provide coating for coils meeting 3,000 HR salt spray resistance test.