

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE 1 OF 4 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0002		3. EFFECTIVE DATE 09/09/07	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 06-0049
6. ISSUED BY Resident Officer in Charge of Construction 1005 Michael Road Camp Lejeune, NC 28547-2521		CODE mks	7. ADMINISTERED BY (If other than Item 6) See Item 6	
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-06-R-0049
			x	9B. DATED (SEE ITEM 11) 08/28/07
				10A. MODIFICATION OF CONTRACT/ORDER NO.
				10B. DATED (SEE ITEM 11)
CODE	FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

06-0049, Major Interior/Exterior Repairs, AS-4035

(CONTINUED)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA (Signature of Contracting Officer)	16C. DATE SIGNED

CONTINUATION SHEET

1. On the fixture schedule they have the type A fixtures call for type 2. There is no type 2 listed for the NL-7 fixture. Please clarify if type A - D.

Answer:

A NL-7 TYPE B

B NL-9 TYPE D

C NL-4 TYPE A

D NL-4 TYPE A

2. Drawing A-4, detail 1/A3/A4, length of wardrobes extend beyond new gypsum board soffit ceiling (see note 36). See non-shaded area of wardrobe on the same detail. Provide construction details of new work.

Answer: Extend the bulkhead above the new CMU closet walls and the soffit throughout the closet area (Extend shaded area to include all of the closet).

3. Inside dimension of wardrobe, per detail 6 on drawing A-4, is only 20" deep. Is this correct?

Answer: Yes.

4. On detail 5 on drawing A-4, bottom blocks of wardrobes to be glazed faced structural tile. We have found that this is not readily available and colors may not match. We have never installed these in any barracks renovations. Will this be required?

Answer: Yes.

5. Detail 2 on drawing A-5 (shower section) shows a bottom outlet drain. This does not match existing and is not what has been installed in previous contracts. Previous contracts required us to install a JR Smith, figure no 6040, reverse angle drain. Is this the drain that will be required to install?

Answer: Install the JR Smith No. 6040 reverse angle drain.

6. Contract drawings require us to provide only 2 new masonry wardrobes. Previous contracts have required us to provide 3 new masonry wardrobes. Is the government's intent to reduce the amount of wardrobes as installed in previous contracts? If 3 wardrobes are required, see note #1.

Answer: Provide 2 wardrobes as shown

7. Drawing P-1, demolition note 3, says "all existing plumbing in the building not shown is to be removed unless noted or indicated otherwise." Note 1 on same drawing clearly tells us what to remove via the demolition legend. Is it the intent of the government for all of the sewer & dwv piping to be demolished and new installed?

Answer: No we are replacing plumbing fixtures.

8. On drawing A-4, Detail 4, the new CMU wall at the sleeping room entrance doors does not include provisions for Damproofing the exterior of the new block walls. Is damproofing required?

Answer: provide damproofing on the exterior face of the CMU exterior walls behind the brick

9. On drawing A-4, Detail 6, the masonry wardrobes do not include provisions for any vertical rebar reinforcement. Is vertical reinforcement required?

Answer: Provide one #4 bar vertically in the cells at the corner, "T" intersection of the new walls and beside each side of each door frame. Fill these cells with mortar as the walls are built.

10. Drawing A-1, note 13, states to "demo CMU wall where plenum is." Please clarify.

Answer: Remove CMU as needed for mechanical installation.

11. Drawing A-3, note 28, calls for "hollow metal doors in wardrobes." Typically we have installed wood doors. Will hollow metal doors be required?

Answer: Yes.

12. Drawing A-3, note 39, calls for metal stair tread nosings. Are we to include the exterior stairways?

Answer: No.

13. Drawing A-11 calls for precast concrete downspout guards. In an effort to match existing at MCAS barracks. Do you have a recommended manufacturer?

Answer: No.

14. The fan powered box & specification does not call for a heating coil. The existing building does not have any hot water piping being run in the soffits, thus the existing boxes do not have a heating coil. On drawing M-7, the last sentence in the sequence of operation for the pressure-independent terminal vav box with velocity controller says "when the space temperature has dropped through the dead band, the duct heater coil shall be gradually controlled to maintain the heating set point as shown." Will the new boxes be required to have heating coils?

If so, we need a drawing showing the how you would like the piping to be run? Also, since there is no existing piping, will the existing HW pumps be sufficient? What size will the pumps have to be now? Will the airtrol system change?

Answer: There is no heat in the fan power boxes. The AHU's will supply the heat. The fan power boxes are vav boxes with a fan and no heat.

15. Drawing A-4, detail 36, tells us to "provide new gyp bd clg ... with new ceiling access panel". HP550 required new access doors to be 3' x 3' 2 door as specified in section 05500. Will we be installing 3' x 3' 2 door access panels?

Answer: Yes.